

14. Decking Procedure

Method of works

Site set up:

- Assess pre-works information from client and/or the contracts manager
- Cordon off area to avoid damage or injury from debris.
- PPE to be worn (gloves/eye protection). Wear face fitted FFP3 mask, where dust may arise. Regular breaks, undertake maintenance of tools.
- Ensure tools and equipment are not acting as a trip hazard.

Removal of old decking:


- Decking Boards:
 - If boards are fixed with screws to joists, carefully unscrew using screw driver or cordless drill with screw driver bit
 - If screws are worn down or boards fixed to posts with nails, a bar is to be used to pry the boards away from the joists.
 - Once boards are removed, they are to be carefully placed to one side ready for disposal, ensuring there are no exposed screws that could be stood on, denial boards and joists in preparation for new boards/safe disposal and handling into lorry/skip.
- Joists and support posts:
 - Using a bar, pry joists from post's and place to one side, ensuring no nails or screws are exposed that could be stood on. If rail needs to be cut while fixed to the post, extra care is to be taken to ensure rail does not drop and uncontrollably to the ground. If this is being completed as a one person job, clamps are to be used to ensure rail does not drop to ground
 - Post is to be cut as close to bottom of concrete base as possible. If a power saw is used, extra support on the post may be required to ensure it does not fall back on the blade or fall uncontrollably onto materials or property
 - Old concrete or spoil to be broken out of ground if specified by client or post is being replaced with like for like. Concrete to be broken out using 110V electric breaker or bolster and hammer as required. Old concrete or spoil to be disposed of unless used for backfill

Installation of new decking:

- Support posts:
 - If end post is being fixed to a wall-
 - Wall is to be checked to ensure suitable fixing can be established and wall is of sound structure to accept the bolt
 - Checks should be made to ensure nothing inside or behind the wall can be effected including electrical appliances
 - Asbestos register to be checked
 - Fence post to be pre-drilled where bolts will go in wall
 - Holes in post to be used to mark-up wall where bolts will be fixed in wall, using a post level to ensure level
 - Holes to be drilled in the wall at the required depth to accept the masonry bolt. Accounting for the width of the fence post. Bolts must be fixed into the wall a minimum of 100% the size of the post. For example, a 75mm post will need a bolt going at least 75mm into the wall. Therefore, a 75mm post will require 150mm bolts. If shorter bolts are to be used these must be counter sunk into the post to ensure there is still the correct length into the wall.
 - Bolts will then be used to fix posts to wall, tightened with hand ratchet or impact driver
 - If end post is set in concrete-


- hole to suit fence post using post shovel to a depth of $\frac{1}{4}$ the length of the post minimum. For example, a 2.4m post will have an hole dug to 600mm
 - Post will be placed in hole with post level fixed to it on the boundary line set out, using timber fixing as a brace to prop level (or second person).
 - Postcrete is to be used in the hole as per manufacturer's instructions, mixing with water and ensuring product is tamped down with tamper
- Once end posts are fixed or set, a string line is to be set up from one post to another.
- Fence post installations are then to be measured out along the string line at intervals as specified by client or as a rule of thumb, 1.8-2m apart. Posts points are to be as evenly spread as possible
- Once positions are marked out for each post, holes are to suit fence post using post shovel to a depth of $\frac{1}{4}$ the length of the post minimum. For example, a 2.4m post will have an hole dug to 600mm
- Post will be placed in hole with post level fixed to it, using timber fixed as a brace to prop level and in line with the string line (or a second person)
- Joist structure:
 - Consider using terram on the ground underneath the decking as a weed supresent.
 - Joists will be placed in between each post, level checked and fixed in position using galvanised screws
 - Structure to be laid out and clamped in position in readiness for fixing, this is also the ideal time to ensure everything is set out square- fix the outer joists together to make the square for the decking to fit on. Then measure outer corner to outer corner diagonally, take not eof the measurement and repeat to the opposite side, both measurements should be the same, if not realign so they are, when they are both equal the frame is then square. **NOTE- diagonal measure will only work if the frame is in a square and both pairs of sides are parallel with each other and the same measurement, (IE- frame is made from 2 x 3m length sand 2 x 4m length's of timber)**

Example-



The measurement from outer corner of the frame on the red arrow should be equal to the measurement of the green arrow- if not realign until they are.

The 3-4-5 triangle can also be used where the frame is not a true square.



- Once the outer joist's are squared up and fixed into place the frame can then be infilled with the supporting joists. Joists are to be set out at 400mm centres and fixed to the outer joists with joist hangers, joist hangers are to be fixed to the timber with square twist nails as manufacturer recommends.
- Joist can then be cut into the frame, joists should be eyed through before cutting and fitment, the joists should be fitted bow up. Once sat in hanger these should also be nailed to the hanger using eth square twist nails.

Decking Boards-

- The first decking board can be laid out parallel with the frame, this is to be fixed using stainless steel screws or specific decking screws that are treated. Alternatively when using composite decking a stainless steel starter clip will be supplied to be used on the first board so fixings are not seen through the top of the board.
 - Carry out a check on every board to make sure the boards are running parallel and not starting to drift, this can be done by measuring the front edge from the start of the first board every time, if they do drift a bit then there will be scope to realign as you continue boarding.
 - Cut ends of timber decking boards are to be treated with five star or end grain preservative as per manufacturers instructions.
 - Repeat process of fitting boards until the joist structure is covered. The final board may need to be a cut board or scribed board to fit.
- Tidy area and remove all waste including offcuts
 - Ensure concrete is covered with soil and cover with grass seed if required

See additional docs

Permit to dig
CAT and Genny Procedure
COSHH

Risk Assessment

| Hazard | Control Measures |
|-----------------------|--|
| Falls from height | See Working At Height If working on a banking or slope, additional control measures may be required which may include fall restraint. This will be picked up in the on-site risk assessment |
| Slips Trips and Falls | The site will remain tidy at all practicable times. All designated access/egress routes shall be kept free of slip and trip hazards, and obstructions. All equipment is switched off and/or isolated when unattended. All material that could potentially cause injury is either secured behind barriers or |

| | |
|-----------------|--|
| | removed from site. The need for good housekeeping is to be explained in the site induction. |
| COSHH | When using any chemicals, the COSHH safety data sheet will be followed to ensure that the safe working practice is followed. This includes storage and use, including the correct use of PPE. Common material sheets are within this document. Additional MSDS may be required for extra chemicals/substances on this contract. |
| REG 8 | Care is to be taken when working near any flues. WMS and subcontractors are to ensure that no flues/ventilation points are blocked (ie taped off/netted etc), and that Reg 8 Gas Safety is adhered to at all times. Any damage at the time of working to any flue/air duct –terminal or debris entering the flue/air duct, condensate pipework, gas installation pipework, gas meter & housings or any part of the heating installation must be reported: Turn off the effected appliance / installation /energy supplies and make safe. After all work is completed re-inspect all flue terminals / installations for damage. Ensure there is no venting appliance in place before any works to the flue/removal of masonry flue. |
| Manual Handling | Correct lifting techniques are to be used at all times when moving equipment, materials or any heavy loads. Paying particular attention when lifting (stable stance, good grip, keep load close to your waist and do not flex your back). 2 person lift to be adopted when lifting large fence posts or other heavier materials. Site supervisor to ensure that mechanical assistance, ie trucks etc are used if objects are too heavy to safely manually handle. |
| Hygiene | Good personal hygiene is a necessity washing of hands prior to any breaks (food – ingestion). |
| Vibration | If there are any tasks with expected high levels of vibration. WMS shall use vibration calculator to work out if operatives are likely to exceed action levels. WMS have assessed these site and there are no excessive vibrating works that are likely have trigger times that will exceed the HSE 100 points. Subcontractors will also assess in their RAMS. Regular breaks between works involving high levels of vibration shall be taken. |
| Noise | If high levels of noise are expected, ear defenders and control measures are to be introduced if lower noise action value is expected to be exceeded (80dB weekly average or 135dB peak). If there are concerns that noise levels are above this, further investigation will be carried out. |
| Respirable Dust | Control measures are to be implemented when any operations are being undertaken that could give rise to respirable dust. Particular attention is to be made to silica dust. When drilling and cutting, dust extraction is to be used to ensure operatives are not working above the 8hr control limit (0.1mg/m ³) and FFP3 masks that have been face fitted to the individual are to be worn. |
| Asbestos | All operatives are to be Asbestos awareness trained. Asbestos surveys are to be sourced and referred to before any works commence. Tradesmen are to remain vigilant at all times when onsite and if any additional suspect materials are identified, site manager is to be informed immediately |
| Excavations | See Cat and Genny Procedure |